

wage earner/job classification may be required from any successful bidder and payroll records must be maintained.

9. **Payment:** One, single, lump sum payment shall be made upon satisfactory completion of the project and submitting all warranty documents to the Owner.
10. **Project Timelines:** Materials may be stored on site after June 22, 2017 with the expressed approval of the Project Contact. The project may begin after July 1, 2017 and must be substantially complete by August 1, 2017.
11. **Mandatory Site Inspection:** Prior to submission of a proposal for the project contemplated in these specifications and accompanying drawings, each bidder shall examine and familiarize himself with all pertinent existing conditions. Surface membrane and substrate boring, testing and resealing the membrane shall be the responsibility of the Bidder. Any and all discovered asbestos and/or otherwise hazardous materials shall be removed and disposed of by the Bidder per applicable regulations at no additional cost to the Owner. The representative core samples of the roofing substrate are known to vary throughout the roof area. Do not rely solely on the supplied approximate dimensions. All drawings and dimensions must be field verified and become the responsibility of the bidder as to each and any site variables. **A mandatory pre-bid site visit must be arranged with the Project Contact.**
12. **Permits and Fees:** It is the responsibility of the bidder to obtain permits of any type required to perform the work. Submit copies to the Project Contact and ISD 361 shall bear the responsibility for payment of any such fees.
13. **Hazardous Materials:** The Contractor shall bring to the attention of the Project Contact any materials required to be removed or disturbed that he may have reason to believe may contain asbestos or any other hazardous material which have not already been so identified by the specification or the Contractor site investigation.

The Contractor and his Subcontractors shall not provide or install any new materials containing asbestos or any other hazardous materials.
14. **Clean-up and Site Restoration:** The Contractor shall keep the defined and surrounding work areas free from accumulation of waste caused by operations of the contract. The Contractor is required to remove from the grounds any and all removed hardware and construction debris. Disposal must take place in an appropriate and legal location.
15. **Tobacco Free Environment:** ISD 361 maintains a tobacco-free environment inside and on the grounds of all their buildings.
16. **Salvage:** The School District shall retain the right to salvage any and all materials removed from this project.
17. **Regulations:** All work and materials must comply with all local, state, federal codes, rules, regulations and laws.

18. **Project Security:** The contractor shall have daily extended time access to areas over evenings and weekends should the Contractor so desire. The Contractor shall be responsible for the security of their equipment and project materials.
19. **Warranties:** In addition to the manufacturer's warranty, the Contractor's materials and workmanship shall be guaranteed for a period of one year from the date of final project accepted completion. **All documentation and paperwork concerning the roof manufacturer/installer 10 year warranty must be submitted with the project invoice prior to any monetary payment.**
20. **Project Scope:**
- a. Strictly adhere to any and all applicable work safety codes in promotion of a safe work zone for both site workers and building occupants.
 - b. Remove roofing layers down to the existing wood fiber, deck insulation of the original roof and dispose of per state and federal codes over any areas where the wood fiber insulation is dry and undamaged. Remove and replace any water damaged wood fiber insulation as necessary down to the metal roof deck. It is believed that a gravel top roof or portions of may lie below the existing surface EPDM.
 - c. Local building code R value must be achieved on all of the replacement area. Any existing **dry, undamaged and intact** wood fiber, foam or iso type board insulation may be reused. **Any supplemental insulation required to meet or exceed local code required R value or to flush lay the area shall be supplied and installed by the Bidder at no additional cost to the Owner.**
 - d. Lay one (1) layer of 1/2" HP board as per manufacturer's specifications.
 - e. Lay and seam .060 EPDM membrane as per manufacturers specifications.
 - f. Flash all penetrations as per manufacturer's specifications.
 - g. Provide and install new pre-finished, color matched metal flashing and counter flashing on exposed roof face over project area.
 - h. Provide and install new tie bar and wall flashing over project area.
 - i. Provide and install roof tie seam to adjacent roof as necessary.
 - j. Provide and install any crickets necessary to eliminate ponding issues.
 - k. Provide and install any missing or damaged drain catch grates or other components.
 - l. Reuse if enough is available and/or install new 2' washed river round ballast rock per manufacturer's recommendation for fully ballasted systems.
 - m. Properly seal any skylights, chimney's or vents

PROPOSAL FORM

The undersigned as bidder hereby proposes, and if this Proposal if accepted, agrees to furnish any and all necessary materials and labor to remove existing and install the new FES roof system per manufacturers installation requirements in accordance with the specification documents for the amount listed below. The undersigned does certify that this Proposal is made without improper connection with any other person or persons making a Proposal on this same purchase, and is in all respects fair and without collusion or fraud, and the undersigned does further declare that no person or persons acting in any official capacity of the Independent School District 361 is directly or indirectly interested therein in any portion of the profits thereof.

Name of Bidding Contractor: _____

Address: _____

Authorized Representative Signature: _____

Date: _____ Phone: _____

Bid Amount: \$ _____